

REQUEST FOR PURCHASE IN EXCESS OF \$20,000/CHANGE ORDER



To: MAYOR AND CITY COUNCIL

Agenda Item #: IV. E.

From: Wayne D. Houle, PE, Director of Engineering

The Recommended Bid is

Within Budget

Not Within Budget

Date: March 5, 2013

Subject: Contract No. ENG 13-2 Normandale Neighborhood Roadway Reconstruction

Date Bid Opened or Quote Received:
February 20, 2013

Bid or Expiration Date:
April 20, 2013

Company:

Amount of Quote or Bid:

Northwest Asphalt, Inc.	\$1,738,562.34
Palda and Sons, Inc.	\$1,855,186.81
Valley Paving, Inc.	\$1,901,059.73
GMH Asphalt Corp.	\$1,969,013.60
Midwest Asphalt Corp.	\$1,995,062.25

Recommended Quote or Bid:

Northwest Asphalt, Inc.	\$1,738,562.34
-------------------------	----------------

General Information:

This project is for street and utility improvements in the Normandale Neighborhood. The project includes spot repairs to existing concrete curb and gutter, reconstructing the existing roadways, storm sewer system repairs, replacing hydrants and gate valves, trunk water main pipe extensions, water and sewer service pipe reconstruction and rehabilitating trunk sanitary sewer pipe. The project was ordered by the Edina City Council at the December 11, 2012 Public Hearing.

This project will be funded by special assessments and respective utility funds. The bid reflects a potential reduction of approximately 30% in City funded costs. At this point in the process we are anticipating the special assessment to be reduced by approximately 22% to \$11,500, versus the \$14,800 that was discussed at the project hearing. This value can change based on construction related items such as soil corrections and turf restoration. The final special assessment will be determined prior to the final assessment hearing.

Turf restoration for all of the 2013 projects will be hydro-seeded versus sodded. See attached memo discussing the selection of hydro-seeding as the turf restoration technique.

Staff recommends awarding the project to Northwest Asphalt, Inc. utilizing hydro-seed for turf establishment.

Attachments:

Turf Establishment in Reconstruction Projects Memo

G:\PWC\CENTRAL SVCS\ENG DIV\PROJECTS\CONTRACTS\2013\ENG 13-2 Normandale\ADMIN\MISC\Item xx Contr No. ENG 13-2 Normandale.docx

Engineering Department • Phone 952-826-0371
Fax 952-826-0392 • www.CityofEdina.com



Date: March 5, 2013
To: Mayor and City Council
From: Wayne D. Houle, PE, Director of Engineering
Re: Turf Establishment in Reconstruction Projects

Summary:

Staff is recommending the use of hydro-seed for the 2013 projects with a revised contractor maintenance period of 90-days. Staff feels hydro-seed will better meet the long term needs of the property owners for turf establishment and at the same time reduce special assessment amounts.

Background Information:

Lawns disturbed by roadway construction have typically been restored with the use of sod. The contractor was responsible for the establishment of sod for a period of 6 weeks (42 days) from the date of installation. After the 6 week maintenance period the property owner is then responsible for the sod.

During 2012, residents and staff noticed portions of the sod installed during the 2011 construction season were not healthy. 2012 saw drought conditions for most of the year. Most of the new sod areas were brown and dormant and/or dead. This reflects badly on the construction project even though continued maintenance of the sod is the responsibility of the homeowner.

Staff hosted a “Construction Contractor Think Tank” meeting. The goal of this meeting was to determine the advantages and disadvantage of sod and hydro-seeding. We wanted a turf product that property owners could perform the proper maintenance on to establish long lasting turf. Staff invited industry experts for this meeting held on January 7, 2013 at the Public Works and Park Maintenance Facility. Attendees included turf experts, contractors, and consultants familiar with City of Edina practices and clients. Topics discussed included watering, maintenance periods, proper long term care, turf color, installation techniques, drought, fertilizer, chemical treatments, equipment, installation dates and foot traffic.

The 2013 bid documents require the Contractor to place 6-inches of topsoil in a level and smooth manner free of stones or other debris that are over 1.5-inches in diameter. Seed, fertilizer, and soil stabilizer is placed in a uniform manner. The Contractor is responsible for mowing the new turf during the maintenance period. The quality of the turf establishment is reviewed after the maintenance period. If the maintenance period does not end by Nov. 1, the remaining balance of the maintenance will carry over and begin on April 15 of the following year. Any turf areas’ deemed unacceptable at the end of the maintenance period will be re-hydro-seeded at no cost to the City.

Staff realizes that resident education and communications is a key component in the establishment of turf using either method; sod or hydro-seed. Construction update letters and City Extra e-mails will



be used to educate the residents on proper maintenance procedures. Turf maintenance is the responsibility of the property owner after the 90-day turf maintenance period.

Table 1. Comparison of Sod and Hydro-Seed

Item	Sod	Hydro-Seed
Cost	\$5.00 - \$6.00 / SY	25-50% less than sod
Water	Equal	Equal
Drought Resistance	Less than seed	Tolerant of dry conditions
Maintenance Identified by Property Owner	Appears complete, less realization of maintenance needs	Maintenance needs are apparent
Color	Some issues, defined line between new and existing turf	Tends to blend with existing turf
Appearance	Appears instant	Established over time
Installation	Labor intensive	Simple
Installation Dates	Not recommended during July / early August but can be accomplished	Not recommended from June 1 until July 20 but can be accomplished
Installation Maintenance Period	90 days recommended	90 days recommended
Foot Traffic	Not an issue	As little as possible until germination
Repairs – Cost	\$5.00 - \$6.00 / SY	25-50% less than sod
Repairs – Installation	Labor intensive	Simple
Repairs – Disturbance	Some	Minimal
Environmental Footprint	Sod is planted off-site, harvested, transported, and replanted.	Hydro-seed is planted on-site and remains on-site.

Based on a research with other communities that use hydro-seed and experience on the West 44th Street project and on information learned from the “Think Tank” session, staff is recommending the use of hydro-seed on the 2013 projects with a revised maintenance period of 90-days. Staff feels hydro-seed will better meet the long term turf needs of the property owners.